

Structure No.	Structure Name	Chainage (m)	Structure Type	Deck Length (m)	Structure Width (m)	Clearance (m)	Description	Estimated Construction Cost (£ / m ²)	Estimated Construction Cost (£)
NRS01	Cockley Road Overbridge	Varies depending upon northern route option	OB	29.00	13.20	5.3 min	Single Span Steel Composite Deck with Reinforced Soil Abutments - Fully or Semi Integral	£4,150	£1,588,620
NRS02	Farm Access Overbridge	Varies depending upon northern route option	OB	25.00	8.40	5.3 min	Single Span Steel Composite Deck with Reinforced Soil Abutments - Fully or Semi Integral	£4,000	£840,000
TOTAL									£2,428,620

Northern Routes Structures

Structure No.	Structure Name	Chainage (m)	Structure Type	Deck Length (m)	Structure Width (m)	Clearance (m)	Description	Estimated Construction Cost (£ / m ²)	Estimated Construction Cost (£)
SRS01	Clarks Lane Overbridge	Approx. 1100	OB	19.20	10.20	5.3 min	Single Span Steel Composite Deck with Reinforced Soil Abutments - Fully or Semi Integral	£4,150	£812,736
SRS02	Charlton Road Overbridge	Approx. 1380	OB	20.88	13.20	5.3 min	Single Span Steel Composite Deck with Reinforced Soil Abutments - Fully or Semi Integral	£4,000	£1,102,464
TOTAL									£1,915,200

Southern Route Structures